



S+H STEEL

F A B R I C A T I O N
& E R E C T I O N



Proposal for: Academy of Math and Science Buckeye - 25382

Contact Us: Estimator - Jacob Odden Cell - 218.341.0265 Email - jacob@shsteelaz.com

Our Values



Committed

Committed to SAFETY,
Ourselves each other,
and our Clients.



Results-Driven Execution

We own it, and get it done
with the end result in mind.



Egos at The Door

We are helpful and humble.
No one graduates from a broom.
Prioritizing your Project over pride.



What's Next?

Proactive.
Innovative.
Growth Oriented.

Differentiators

- 1.** Rapid Schedule
- 2.** Proactive Communication
- 3.** A Partner Who Keeps Agreements

***Details that support
your next decision. >>>>***

Date: 09/22/25

Quote # 25382

Attention: Estimating

Addenda Acknowledged: No

The Following Items Will Be Furnished and Installed:

1. Columns
 - a. C1 – anchor bolts and templates as FOB
2. W24x55 beams
 - a. Beam seats per 4 & 5/S4.0 as FOB
3. Plate and ledger per 9/S4.0
4. HSS between joists per 10/S4.0
5. Joists
 - a. Joist seats per 1 & 3/S4.0 as FOB
6. Deck
7. Ledger per 2/S4.0
 - a. Embeds as FOB
8. Mechanical unit frames per 4/S1.4
9. Roof drain frames
10. Metal canopy frames per 5-7/S3.0
 - a. Standing seam cladding by others
11. Roof-access ladder
12. Notes:
 - a. All lintels assumed to be masonry – by others
 - b. Site fence and gates by others

We appreciate the opportunity to quote this project.

Respectfully,

Jacob H. Odden
S&H Steel Co. LLC
AISC Certified Fabricator
City of Phoenix Approved

S & H Steel is an AISC Certified Shop and Erector

This proposal was based off architectural and structural drawings dated 06/10/25.

Raw material and fuel prices are based on current prices at the date of this proposal. Any significant price increases (meaning a price increase exceeding 5%) on materials and/fuel necessary to perform the work, that occur during the period of time between the date of this proposal and substantial completion of the project, shall cause the contract to

be equitably adjusted by an amount reasonably necessary to cover the increase. S&H shall provide to the buyer a copy of the relevant material price increases or fuel surcharge from S&H suppliers as proof of such increase.

Terms and Conditions:

1. No state, county or city sales taxes are included in this bid.
2. All coated steel to be standard shop primed unless noted otherwise; standard primer is Sunburst Series #38– compatible with WB4 intumescent paint.
3. This proposal is subject to acceptance within 10 days from this date tendered and shall be subject to satisfactory arrangement of details. The Code of Standard Practice of the American Institute of Steel Construction, Fifteenth Edition, 2016, is hereby made a part of this proposal and shall govern in all matters to which it is applicable not otherwise provided herein.
4. If accepted, this proposal and our quote number shall be part of any future contract or purchase order resulting from this quote.
5. If erection is included in this quote, level, clean and safe access shall be provided for erection equipment and materials.
6. If project is TI or remodel work in existing conditions, S&H assumes having adequate access for erection, laydown, equipment, etc. – we reserve the right to revise this proposal should S&H deem access inadequate.
7. If project is TI or remodel work in existing conditions, this proposal should not be considered valid until a site visit can be made to confirm site conditions, and means/methods assumed for listed scope above.
8. All line and grade shall be the responsibility of others. Per AISC, prior to column erection, one (1) grade nut at each bolt cluster shall be set at proper elevation by Customer. If leveling plates are used, Customer shall set plates to grade.
9. All existing materials that connect to our steel must be open and accessible from the floor.
10. All existing materials that connect to our steel must be clean and ready for our materials to connect thereto. Removal and reinstallation of fireproofing, paint, etc. is not part of S & H's scope of work.
11. See our list of standard exclusions attached with this proposal for other exclusions.

S&H STEEL CO. LLC

The following items are **excluded** from or are a **clarification** to the “Scope of Work” portion of the contract between the General Contractor and S&H Steel.

Exclusions:

1. All demolition, cutting, patching, repairing, and shoring.
2. All grout and dry pack.
3. Roof hatches and ladder ups.
4. Sign frames & signage .
5. All gates and fencing.
6. Louver systems.
7. Standing seam and pre-finished metal decking.
8. Light poles with bases and bolts.
9. All name brand grates such as NEMA, all ornamental tree grates and walker duct type systems.
10. Application of “Bondo” on AESS steel. If the project specifically requires the application of S&H Steel perform the work for the cost of Time and Material.

11. Cold rolled structural steel framing, load bearing metal stud systems, light and heavy gauge metals, clips, attachments, purlins, etc.
12. All light gauge framing 12-gauge and lighter, including metal studs, joist, fascia, soffit, gutters, down spouts, flashing and all architectural decks and metal materials used as roofing, fascia, soffit, siding, or suspended ceilings. All decks with pre-finished surfaces such as Kynar paint finish. All specialty type decks which are not fabricated by Verco Deck Manufacturing Co. And all sheet metal materials.
13. Bolts, fasteners, templates and embeds not used to fasten S & H Steel's product to the structure.
14. All non-ferrous metals such as stainless, brass, copper, aluminum, and chromed finishes unless otherwise noted. This includes ladders, vanity and shelf brackets handrails and other types of architectural pieces.
15. All steel lintels for wall penetrations not individually shown on the structural drawings.
16. Locking devices for gates such as deadbolts, pad locks and panic hardware.
17. All flagpoles, signposts, playground equipment and TV support brackets.
18. All stair nosing.
19. All Simpson-type hangers and saddles.
20. All shoring of deck and structural steel for concrete pours.
21. All steel items including gates, pipe bollards, fencing and railing only shown on the Civil, L, M, P & E drawings are excluded unless prior arrangements have been made.
22. All required bonds are to be paid by the general contractor.
23. All MAG, city, county, or state spec. Steel not specifically shown on the A or S drawings.
24. All finish paints. Also, all finished paint preparation covered under the Painting sub-contractors' scope of work as outlined in the finished paint section of the specifications. This includes the removal of dust, dirt, mud, scratches, dings, burn marks and primer chips, scratches and gouges caused shipping, storing handling and installation.
25. Special surface preparation such as sand blasting, and special primer other than standard shop primer.
26. Special treatment to steel to enhance/accelerate oxidation.

Clarifications:

27. Material is procured from approved-for-fabrication drawings only. Early procurement is possible at the GC's request and risk.
28. This proposal is based on an appropriate schedule; whether given, discussed, or assumed. Should the project push beyond a reasonable time, S&H reserves the right to re-price, adjust, or re-assess our portion of the project.
29. S&H operates under strict and safe guidelines in the field; any specialty safety equipment required for a jobsite, if not previously disclosed, will be accounted for via change order.
30. Mechanical framing for roof and floor penetrations, and mechanical equipment located on the roof or floor will be provided by S&H Steel. However, the exact sizes and dimensions of all penetrations must be provided for this framing prior to the installation of the deck. All material required to support suspended mechanical equipment including angles, channels, unistruts and hangers that attach to the structural steel for hanging suspended mechanical equipment and piping is excluded.
31. Steel lintels weighing less than 250 Lb. are FOB the job site.
32. Insulation strips for acoustical deck are F.O.B. the job site.
33. The drilling, punching, or burning of holes in our steel for other trades, including holes for operable walls, are assumed to be by others unless arrangements have been made prior to the installation of steel.
34. All vanity brackets, shelf brackets and countertop steel framing pieces, if included in quote, are F.O.B. the job site.

35. All temporary safety rails and cabling for use by the general contractor and other trades is excluded from our scope of work. S&H Steel provides OSHA cabling only for our use as we deem necessary per OSHA requirements during our phase of construction. Maintenance and removal of safety cable, after S&H scope is complete, is by others.
36. No temporary safety cable is assumed on roof level.
37. General Contractor must assume reasonable responsibility to protect existing floors ceilings, walls, furniture, fixtures, equipment, and other exposed architectural finishes in all pre-existing and remodeled buildings. S&H Steel will do the same.
38. Steel Joist, Trusses and Girders are long-lead items; fabrication drawings for approval and fabrication will be dependent upon current market standards. As such, S&H Steel requires project scheduling to incorporate the joist drawing and fabrication schedule into our scope of the work.
39. Steel decking is a long-lead item; fabrication drawings for approval and fabrication will be dependent upon current market standards. As such, S&H Steel requires project scheduling to incorporate the Deck drawing and fabrication schedule into our scope of the work.
40. Detailing is generally a long-lead item; fabrication drawings for submittal plus additional time required for scrubbing the drawings once they are returned from the approval process will be dependent upon current market standards. As such, S&H Steel requires project scheduling to incorporate the detailing process into our scope of the work. All drawings must be released for fabrication prior to S&H Steel proceeding with fabrication. To avoid problems S&H Steel should be consulted prior to job schedules being formatted.
41. Due to the Volatility of material pricing and availability, S&H Steel will issue purchase orders for as much material as possible i.e., steel, joist, deck, fasteners, etc. at the time authorization to proceed with the project is given from the General Contractor to S&H Steel. If requested by S&H Steel, the General Contractor must agree to pay for this material net 30 day regardless of if the material has been fabricated or shipped to the job site. S&H Steel will provide insurance, invoices, and other documentation as needed for the G.C. to meet this requirement.
42. Some steel items such as Steel Joist, Structural Metal Decks, Grating Products, Perforated Plates and Gate Hardware are fabricated by manufacturing companies. Their products are manufactured to industry standards. For example: Steel Joist are manufactured to SJI standards, Structural Metal Deck is manufactured to SDI standards and so forth. S&H Steel has no control over the governing boards which establish the standards for these products. If faulty material or workmanship is discovered in the described products, S&H Steel will direct the manufacturer of the faulty items to make right through the warranty process any defects in the material.
43. It is the General Contractors responsibility to inform all trades attaching products such as HVAC equipment, Piping, duct work, etc. which weighs in excess of 100 lb. to any joist, girders, or trusses that the product must be attached within 3 inches of a joist girder or truss panel point. Attachment to bridging is not allowed. As such, S&H Steel is not responsible for any structural modifications i.e., adding additional panel points or beefing up joist girders, and trusses when products are attached to the panel point beyond the 3" limit.
44. S&H Steel makes every effort to meet the various G.C. certificate of insurance requirements on every job. However, in the event a G.C. has insurance requirements contractually specified which are not reasonably possible for S&H Steel or its insurance company to provide, the G.C. will accept S&H Steel insurance certificate as issued by our insurance provider in the dollar amounts proscribed in the contract without penalty to S&H Steel.
45. Monetary retention when held from the contract monthly draws shall be paid as outlined in Arizona. Statute 34-221 paragraph B section 3 only if applicable to this project.
46. S&H Steel is not in the design sector of the construction business. As such, S&H Steel specificity excludes all engineering and special connection requirements which are not

designed and shown on the contract documents by the engineer or architect of record as part of our work unless agreed to in writing at bid time.

S&H Steel makes no assumption that we know and or understand all codes and standards related to our scope of work imposed by local, state national and federal entities. We therefore assume no responsibility for design errors in the contract documents.